Inova Center for Personalized Health Sewer Line Improvement

July 2025





Project Team

















Inova Center for Personalized Health background

- 2015 Inova purchases the property from ExxonMobil and begins renovations of existing 1.2 million square feet
- Spring 2019 Inova Schar Cancer opens
- Fall 2019 Fairfax County approves Comprehensive Plan Amendment and related zoning applications to allow for mixed-use development
- Winter 2020 utilized as COVID-19 Vaccination Center
- Feb. 2025 UVA | Northern Virginia opens on campus
- June 2025 reaching existing campus capacity






Preparing for the future

- This campus (and parts of Inova Fairfax Hospital) currently served by an at-capacity sewer line
 - Existing sewer line runs across the southern portion of the ICPH, under the Beltway, and then through easements between the Fairview Park commercial and residential properties
- Current sewer line must be replaced before any future development can take place
- Inova preparing to replace the current 10" line with an 18" line
 - Will tie in with a 27" regional interceptor on the eastern end
- Existing residential and commercial sewer service will not be affected
- Coordinated with Fairfax County, Fairfax County Park Authority, and Virginia Department of Transportation on all necessary approvals and permits




Project summary






Limits of clearing and grading (shaded area)






Freehollow Drive / Pathway Court Section





Holly Berry Court Section






Tree removal & revegetation

- Inova section
 - 51 trees shown for removal (of those required to be counted) 7 of which are dead or damaged
- Holmes Run Woods West section
 - 58 trees shown for removal (of those required to be counted) 10 of which are dead or damaged
 - Revegetation to include 156 new plantings
 - * 78 shrubs (Red Chokeberry, Buttonbush, Sweet Pepperbush, Silky Dogwood, Witch Hazel, Swamp Azalea)
 - 52 understory trees (Downy Serviceberry, Eastern Redbud, American Hornbeam, White Fringetree, American Holly, Eastern Hornbeam)
 - 26 overstory trees (Red Maple, Persimmon, Tulip Poplar, Tupelo, Swamp White Oak, Willow Oak)




Revegetation Freehollow Drive / Pathway Court Section





Revegetation Holly Berry Court Section





Project Timeline

- June 2025: County preconstruction meeting on Inova section
- July 2025: Community outreach
- July 2025: County preconstruction meeting on Fairview Park section
- Late summer 2025:
 Construction work to begin
- Summer 2026: Majority of project completed with plantings to begin

Work hours:

- Monday Friday
- 7 a.m. 5 p.m. most days
- We appreciate your patience as we work through this improvement.

Learn more / keep in touch

Project Page:

https://www.inova.org/locations/inova-center-personalized-health/progress-updates

Project contact:

- Dominic Bonaiuto, Director, Government & Community Relations
- Dominic.Bonaiuto@inova.org
- 571-331-2952

Thank you

